BITUMINOUS CONCRETE APRON AND PARKING

3 HANDICAP ACCESSIBLE PARKING SPACES (2 VEHICLE AND 1 VAN)

UTILITY SERVICE CONNECTION INSTALLED TO MEET ALL APPLICABLE ELECTRIC CODES

2 - 1 1/2" SCH 40 PVC CONDUITS WITH PULL LINES FROM METER PANEL TO SCOREBOARD.

PROCESSED AGGREGATE PARKING AREA

**PROPOSED PARKING**
(86 PARKING SPACES)

PROCESSED AGGREGATE PARKING AREA

LIMIT OF BITUMINOUS PAVEMENT (TYP.)

190 LF OF TIMBER GUIDE RAIL (ADD ALTERNATE #2)

SCOREBOARD

CONCRETE SIDEWALK

HANDICAP PARKING SIGN (TYP. OF 4)

PROPOSED TRENCH DRAIN (ADD ALTERNATE #1)

2-1½" SCH 40 CONDUITS WITH PULL LINES

END CONCRETE SIDEWALK AND BEGIN BITUMINOUS CONCRETE SIDEWALK

12"x 12" UTILITY HANDHOLE WITH TRAFFIC RATED COVER (LOCATION TO BE DETERMINED IN FIELD)

PROPOSED RAIN GARDEN DESIGNED TO HANDLE 1" RAINFALL EVENT (CALCULATIONS BASED ON PARKING AREA BEING COMPLETELY PAVED) AREA TO BE SEEDED WITH NEW ENGLAND WETLAND PLANTS WET MEADOW SEED MIX

RIPRAP APRON

RIPRAP SPILLWAY

10' WIDE SWING GATE (TYP. OF 2)

DUGOUT ON CONCRETE PAD WITH CHAIN LINK FENCE SIDES AND WOODEN ROOF. (TYP. OF 2). SEE DETAIL

5' WIDE BITUMINOUS CONCRETE SIDEWALK

BACKSTOP FENCING

FOUL BALL ACCESS (TYP. OF 2)

75' UPLAND REVIEW AREA

BLEACHERS ON BITUMINOUS PAD (TYP. OF 2)

SCALE: 1"= 20'

## WETLAND & U.R.A. IMPACT TABLE

| | |
|---|---|
| DIRECT WETLAND IMPACT | |
| UPLAND REVIEW AREA DISTURBANCES | |
| UPLAND REVIEW AREA RESTORATION | |

## GENERAL NOTES:

1. WETLANDS WERE DELINEATED BY NEW ENGLAND ENVIRONMENTAL SERVICES IN SEPTEMBER 2021.
2. FIELD SURVEY WAS PERFORMED BY BARTON AND LOGUIDICE, LLC IN OCTOBER 2021.

J:\3039\10 Softball Field Feasibility Study\Design\PLOT_Coventry Softball Field_Transfer Station.dgn


Barton & Loguidice
41 Sequin Drive
Glastonbury, CT 06033
Phone: (860) 633-8770
Fax: (860) 633-5971
www.bandlct.com
Civil Engineering • Environmental Consulting • Land Surveying • Construction Management


| | |
|---|---|
| PROJ. ENGINEER | MJP |
| PROJ. MANAGER | KRG |
| OFFICE REVIEW | KRG |
| REVISIONS | |
| SCALE: | 1"= 20' |

**SOFTBALL FIELD PROJECT**
PREPARED FOR
TOWN OF COVENTRY
**SITE DEVELOPMENT PLAN**
CT ROUTE 31 - MAIN STREET — COVENTRY, CT

| PROJECT | DATE | SHEET NO. | OF |
|---|---|---|---|
| 3039-010 | 06/15/22 | 2 | 6 |